



**OFFICE OF THE EXECUTIVE ENGINEER (JHOTWARA ZONE)**  
**NAGAR NIGAM GREATER, JAIPUR**

**NAME OF WORK :-** वार्ड नं. 60 में स्थित जगदम्बा नगर बी में सी.सी. सडक का निर्माण कार्य।

**G-SCHEDULE**

Based on RUIDP BSR 2017

S. No	Particulars	Qty	Rate	Unit	Amount in Rs.
1	Earth work in excavation for roadway, including trimming bottom and side slopes in accordance with requirement of line, grades and cross sections, including disposal of surplus material with all lift and lead upto 1000 metre as per MoRT&H specification clause 301. In all type of soil	336.00	145.00	Cum	48720.00
2	Carriage of Materials by mechanical transport including loading, unloading and stacking :: Earth 5.0 km	336.00	165.00	Cum	55440.00
3	Providing and laying lean cement concrete 1:4:8 in Sub- base over a prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 150 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in concrete mixer, laid manually, compacted with surface vibrator, finishing and curing complete as per clause 601, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion.	134.00	2300.00	Cum	308200.00
4	Providing and laying un-reinforced, dowel jointed, plain cementconcrete mix in pavement over a prepared sub base with 43 grade cement, coarse and fine aggregate conforming to IS: 383, maximsize of coarse aggregate not exceeding 25 mm, mixed in a batchin and mixing plant as per approved mix design, transported to site,laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision ofcontractioexpansion, construction and longitudinal joints, joint filler separatio membrane, sealant primer, joint sealant, debonding strip, dowel bar tie rod, admixtures as approved, curing compound, finishing to linesand grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion.PCC M-20.	192.00	5560.00	Cum	1067520.00
5	Providing, laying, spreading and compacting of granular sub-base by providing close graded material (Table 400 1), spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per MoRT&H specification clause - 401 including all material, labour, machinery, lighting, guarding and maintenance of diversion Grading - III Material	94.00	813.00	Cum	76422.00
			<b>Total</b>		<b>1556302.00</b>

  
**EXECUTIVE ENGINEER (JHOTWARA ZONE)**  
**NAGAR NIGAM GREATER , JAIPUR**

I/We hereby accepted rates

..... % above/below as per G-Schedule

Signature of the contractor with full postal address